

F - ROZPIS VÝMĚR - VEDLEJŠÍ PLOCHY 0.350-1.002 KM

Stavba: II/316 - Kostelec n/O. - 2. etapa SO 101.2. Komunikace - Rekonstrukce

strana:10

Staničení	ACO11+ 40 mm	ACO11+ 50 mm	ACL16+ 50 mm	ACP22+ 50 mm	ACP22+ 60 mm	MZK 150 mm	Šda 250 mm	Šda 200 mm	frézování 50 mm	odstran. živ.vr.100	odstran. podkl. 200	výztuž mříž	postřik 0.5 kg/m2	odstran. kostky	dlažba z kostky	výkop	pozn.
353-358	8,00				8,00			8,00		8,00	8,00		8,00				vedl. plocha L
		10,00							10,00				10,00				MK Stradinská
			20,00	10,00		10,00	10,00		20,00			20,00	40,00				oprava překopu
																	MK Stradinská
			20,00	10,00		10,00	10,00		20,00			20,00	40,00				oprava překopu
																	MK Stradinská
444,00		90,00							90,00				90,00				rozjezd MK P
447-452			2,00	2,00		2,00	2,00									1,00	rozšíř. kom.
515.8-520			7,50	7,50		7,50	7,50									4,00	rozšíř. kom.
503,00			3,00	3,00		3,00	3,00									12,60	rozšíř. kom.
511,00		50,00							50,00				50,00				rozjezd MK P
			14,00	7,00		7,00	7,00		14,00			14,00	28,00				oprava překopu
																	MK Katovská
			24,00	12,00		12,00	12,00		24,00			24,00	48,00				oprava překopu
																	MK Katovská
500,00								50,00			50,00			50,00	50,00	8,00	rozjezd MK L
			24,00	12,00		12,00	12,00		24,00			24,00	24,00				oprava překopu
																	MK Chaloupkova
545,00		130,00							130,00				130,00				rozjezd sil. P
																	III/3162
604,00		15,00	15,00	15,00		15,00	15,00			15,00	30,00		30,00			3,00	rozjezd MK P
637,00		20,00							20,00				20,00				rozjezd MK L
			10,00	5,00		5,00	5,00		10,00			10,00	20,00				oprava překopu
																	MK L
			10,00	5,00		5,00	5,00		10,00			10,00	20,00				oprava překopu
																	MK L
715,00							38,00				38,00			38,00	38,00	5,30	rozjezd MK P
716,00		65,00	65,00	65,00		65,00	65,00			65,00	65,00		130,00			14,60	rozjezd MK L
854,00		25,00							25,00				25,00				rozjezd MK P
																	Na spravedlnosti
858,00		25,00	25,00	25,00		25,00	25,00			25,00	50,00		50,00				rozjezd MK L
905,00		40,00	40,00						40,00				40,00				rozjezd MK P
																	Na Vrbíně
976,00		30,00	30,00	30,00		30,00	30,00				60,00		60,00				rozjezd MK P
1002,00																	
CELKEM	8,00	500,00	309,50	208,50	8,00	208,50	246,50	58,00	487,00	113,00	301,00	122,00	863,00	88,00	88,00	48,50	
						205,50	infiltr. postř. 1.0				odstranění podkl. 0.15			88,00	bez dod.		
							243,50	58,00	úprava pláně						88,00	ŠD 250 MM	



